

#### DRAWING TITLE

# JUTA X8 CDM Termination Detail - Option B

### NOTES

- Detail is generic to application so should be used as a guide not a specific installation detail.

  JUTA Cavity Drain systems should be installed by suitably experience waterproofing contractors. Please contact JUTA for Specialist Contractors Details

  JUTA Perimeter Channels must be maintainable and installed to include minimum 1 outlet per 50/m of perimeter channel. A minimum of 2 outlets must be provided as a minimum

  Cleaning ports / Jetting eyes must be provided to JUTA Perimeter Channel at every 12/m or change in direction. For further detail see typical access port detail

  All new concrete surfaces must be treated with anti-lime coating to prevent leaching of free lime & mineral salts.

  All design decisions made by others that might have an impact on the gas and waterproof design performance should be brought to the attention of the design team and Juta UK Ltd. Final decisions and/or any recommendations should be approved by the design team and Juta UK Ltd.

  Dimensions are not to be scaled from this drawing. All written measurements are to be checked on site by the contractor.

  All rights described in chapter IV of the copyright, design and patents act 1988 have been generally asserted.

### DRAWING NUMBER

# JUTA.CDM.014-B

DRAWN BY CHECKED BY SCALE DATE PD Not to Scale Nov 2019



MELTON GROVE WORKS **BLACKPOOL ROAD** LYTHAM FY8 5PL

Tel: 01772 754177