

NB- All DPC's & membranes interrupting masonry bed joints are required to be bedded above and below with mortar.

